




1. THE REMOVAL OF EXISTING CONCRETE CURB, GUTTER, SIDEWALK AND PAVEMENT FOR PEDESTRIAN RAMP INSTALLATION SHALL COMPLY WITH SAN DIEGO REGIONAL STANDARD DRAWING G-11.
2. AREAS SHOWN THUS :  SHALL HAVE A HEAVY BROOM "RIPPLE" TEXTURE FINISH, TRANSVERSE TO AXIS OF RAMP.
3. AREAS SHOWN THUS :  ARE THE MINIMUM REQUIRED FOR A COMPLETE RAMP INSTALLATION AND SHALL BE CONCRETE CLASS 520-C-2500.
4. IF OBSTRUCTIONS SUCH AS INLETS, UTILITY POLES, FIRE HYDRANTS, ETC., ARE ENCOUNTERED, THE RAMP LOCATIONS MAY BE ADJUSTED UPON THE APPROVAL OF THE ENGINEER.
5. RAMP SLOPE SHALL NOT BE FLATTER THAN 15:1.

Revised:	Original approval date: 3-23-94	CITY OF CHULA VISTA PUBLIC WORKS DEPARTMENT	
	Redrawn By: CVM Date: 8-21-01		
			GENERAL NOTES FOR PEDESTRIAN RAMPS
	CITY ENGINEER Date: 11-7-02		
			CVCS 29